

OPERA SAN JOSE
Falstaff Set Rental Information
DRAFT 12/9/13

FEES:

Scenery and Services Fee: \$27,000 (per two week rental)
Designer Royalty: Included
Additional Performances: \$5,000-\$7,000 (per additional week)

Trailer Load/Unload crew fee: \$2,000
Insurance Required: \$100,000 listing OSJ as additionally insured

Technical Supervisor \$250 per travel day, \$400 per working day, \$50 daily per diem, housing and travel

TRANSPORTATION:

Number/Type of Box Trailers: 1 - 53' Box Trailer & 1 - LTL (size currently TBD)
OSJ preferred transportation servc Roadshow, 1-800-861-3111, Jason Curtis

CREW REQUIREMENTS:

Below is the union crew used by OSJ for their production of this opera.
Crew sizes may vary for the renting company based on it's schedule, theater, union contract, loading dock, etc.

	Lighting	Load-in	Set Load-in 1	Set Load-in 2	Lighting Focus	Run Crew	Load-out 1	Load-out 2
Flyperson	1	2		1	1	1	2	1
Electricians	8	1		1	8		4	8
Pig Loaders	2	2		2			2	2
Carpenters	2	12		8		4	12	8
A/V					1		1	0
Board Operator						1		0
Spot Operators						2		0
Prop Runner					1	1		0
Approximate Time	8 hours	8 hours	8 hours	10 hours	N/A	5 hours	8 hours	

ORIGINAL THEATER INFORMATION:

Wall to wall width: 156'-8"
Width within Stage house: 92'-6"
Wing width SR: 29'-6"
Wing width SL: 19'-0"
of linesets: 59
Size of loading door: 11'W x 15'H
Depth of Apron: 7'-11 3/4"
Depth (PL to back wall): 41'-2"
Depth (PL to last lineset): 40'-7"
Height of grid: 87'-4"
Height of supertitle screen bottom: 20'-0"
Width of Proscenium: 43'-11"

SET TECHNICAL INFORMATION:

Mimum Width: 83'-0"
Mimum Depth: 36'-1"
Total # of linesets used: 29
Linesets for scenery: 12
Linesets for electrics (no electrics): 8
Linesets for masking (no masking): 8
Height of tallest drop: N/A
Tripping of drops permitted: NO
Furthest upstage flying piece: 36'-1" (Moonbox)
Weight of heaviest flying piece: 2400 lbs (Portal 2)
Dimensions of largest flying piece: 63'W x 25'H
Dimensions of largest soft piece: N/A
Dimensions of largest ground units: 27'-7 1/2" x 4'-0" (Step Unit)

ADDITIONAL NOTES:

Supertitle screen not included in rental
No House softgoods included in rental
Step unit ships as 3'-9 1/2" x 16'-7 1/2", 800 lb single unit
Porrtal walls all ship in 25'-0" lengths, heaviest piece weighs 315 lbs
2 personnel lifts must be supplied by renting company for load-in and load-out
14 moving carts must be supplied by renting company for load-in and load-out

Estimated costs subject to change and may vary. Final costs will be set with contract.

For further set rental information please call John Draginoff at 310-564-6360 or email draginoff@operasj.org